



MUNICIPAL CORPORATION OF GREATER MUMBAI

**Tender Subject:- SITC of Light fitting, Wiring and allied Electrification Work at
Chembur Fish Market, under M West Ward, Chembur,
Mumbai**

Eligibility Criteria:- As per tender notice

Due date – 01.08.2024

EMD amount- Rs.3000

Tender Fee- Rs. 330 +18% GST

Spot Quotation no -

Office Address:

Office of Assistant Commissioner M/West ward

M ward office Building,

Sharadbhau Acharya Marg

Chembur (E) Mumbai-400071

Ph. No. 022-2522500 Extn.-139

Fax-022-25270148

Email:- ae01swm.mw@mcgm.gov.in

Note:

1. All applicable taxes shall be considered before quoting the rates for the tender
2. The tenderer should quote the tender as per GCC contract
3. The GCC contract will be applicable to successful bidder & same is available on the MCGM website i.e. portal.mcgm.gov.in
4. Security Deposit:- The successful bidder will have to pay security deposit @2% of total contract price as security deposit for faithful performance of the contract. Such contract deposit shall be either in the form of Demand draft or tenderer shall pay such contract deposit online & same shall be refunded on successful completion of the work. However the contractor shall have to submit bankers Guarantee (BG) of equivalent amount valid for a period of one year against which the contract deposit shall be refunded.

In case of rebate of more than 12% of the office estimate, however such contract deposit shall be refunded after a period of 1 year after completion of work. It is however necessary to issue a certificate before refunding the contract deposit in such cases that the quality of the work carried out is up to the mark & no defects have been observed during this period.

5. The successful tenderer should submit the affidavit on Rs. 500/- stamp paper stating that they will submit valid insurance policy i.e. work contract policy , CAR policy in due course of time.
6. The tenderer quoting rebate of premium more than 15% of the office estimated cost should submit the rate analysis to the office of AE(SWM)M/W within 24 hrs. after opening the bid and if it is not workable then the penalty of Rs. 5000/- each for first 3 instances will be recovered from the vendor's registration deposit or from his dues with MCGM. If continuation of such offences is observed, then the action of blacklisting the vendor shall be initiated by concerned ward.
7. If successful tenderer do not submit the requisite documents like, authorization certificate, Experience certificate , Performance Gurantee, affidavit etc. within three days, the offer of L-1 will be cancelled. Further their security deposit will be forfeited & will be debbarred for next 3 years and offer of L-2 bidder will be accepted.

8. **Additional Security Deposit:-**

The tenderer quoting the rebate more than 12% of the office estimate shall have to pay ASD for the entire amount calculated as per the formula given below without any maximum limit.

$$ASD = \frac{1 \times X \times \text{office estimated cost}}{100}$$

Where X= percentage rebate quoted on the office estimated cost by the tenderer minus 12%

9. **Refund of ASD:-**

ASD obtained from successful tenderer shall invariably be, refunded after successful completion of work in all respect or after the submission of the bill, whichever is later

10. **Performance Bank Guarantee:-**

% Quoted	Amount of P.G.
Any Premium or at par	3% of contract sum
Rebate up to 15%	3% of contract sum
Rebate up to 15.01 % to 20%	10% of contract sum
Rebate from 20.01% and above	20% of contract sum

11. **Technical Specifications, Terms & conditions:-**

The work covered by these specifications Temporary Arrangement of CCTV Camera for Ambedkar Jayanti at Dr. Babasaheb Ambedkar Garden in M/West ward

- A. The tendered should have M & E class B Register contractor in MCGM
- B. The contractor should have PWD electrical license.
- C. The contractor should have work experience & similar work
 - a). 40% estimated single work order
 - b). 25% Two work order
 - c) 20% Three work order
- D. All electrical material, which will be used in electrification work shall be of MCGM approve quality (ISO mark) or reputed manufacturer in Indian market
- E. All tools & materials required for the job shall be arranged by successful contractor.
- F. Any minor work arising during the execution of the job shall be carried out by the successful tendered as his own cost.
- G. Transportation, security & + material is a Contractors responsibility.
- H. MCGM shall not be held responsible for any mishap /accident occurred to men in material of the successful tendered during the contract period of the work order given.
- I. The contractor should submit audit and turn over solvency document

Municipal Corporation of Greater Mumbai

Sub :- SITC of Light fitting, Wiring and allied Electrification Work at Chembur Fish Market, under M West Ward, Chembur, Mumbai

Sr. No	USR Code	Description of item	Qty	Rate Inc. GST	Unit	Amount
1	R3-ME-4-28-a	SITC LED Flood Light Fitting -150 W Nos 9600	9		Nos	
2	R3-ME-4-34-a	LED Tubelight fixtures 1X 18W	20		nos	
3	R3-ME-4-27-c	Outdoor LED Street Light fittings – 36-48 W Nos 3459	2		Nos	
4	R3-ME-2-5-k	1 st category Submersible flat cable – 4C x 6 Sq.mm	60		nos	
5	R3-ME-2-3-e	1 st category Cu armoured cables FRLS outer sheathed- 2C x 2.5 Sq.mm	320		Rmt	
6	R3-ME-2-22-b	Supply & Laying of double wall corrugated (DWC) pipe 63 mm OD / 51 mm I.D.	55		Rmt	
7	R3-ME-10-9-c	Embedded Junction Box with 4way connector suitable for cable upto 3Cx16 Sq.mm cable	1		nos	
8	R3-ME-1-19-a	16/32 Amp. DP MCB Nos 3049	9		nos	
9	R3-ME-1-19-c	63 Amp. TPN MCB Nos 5271	2		nos	
10	R3-ME-9-97	MS structure for AC works Kg 260	40		kg	
11	R3-ME-7-1-c	Earthing station with 600 mm x 600 mm x 6 mm galvanised iron plate & 50 mm dia. G.I. pipe, 3000mm long GI pipe (Class B or better) earth pit as per IS 3043. The earth pit shall be provided with watering pipe (Class B) with wire messed funnel, 25x3 GI strip/ / 2X8SWG G.I. wire up to chamber (wire or strip size as per fault level), isconnecting links with 600 x 600 mm (clear) RCC chamber & heavy duty 3mm thick CI chequered plate cover with hinge & stainless steel bolts. Bentonite/ Charcol & Salt shall be provided for earth pits. Excavation, back filling, removal of excess soil is included in the scope	1		nos	
12	R3-ME-7-4-e	Earthing Continuity Conductors -25 x 3mm GI	15		Rmt	
Estimated Cost of the work						
Total Rs.						
GST 18%						
Total Cost of work Rs.						