

Brihanmumbai Mahanagarpalika

Tender Subject:- Temporary Arrangment of CCTV Camera and Lighting and PA System at Charai Talav for Dasara Festival 2024 in M/W Ward

Eligibility Criteria:- As per tender notice Due date – EMD amout- Rs. 3300 Tender Fee- Rs. 330+18% GST Sanction no.- MDM/P/ 3209/

Office Address:

Office of Assistant Commissioner M/West ward M ward office Building, Sharadbhau Acharya Marg Chembur (E) Mumbai-400071 Ph. No. 022-2522500 Extn.-139 Fax-022-25270148

Email:- ae01swm.mw@mcgm.gov.in

Note:

- 1. All applicable taxes shall be considered before quoting the rates for the tender
- 2. The tenderer should quote the tender as per GCC contract
- 3. The GCC contract will be applicable to successful bidder & same is available on the MCGM website i.e. portal.mcgm.gov.in
- 4. Security Deposit:- The successful bidder will have to pay security deposit @2% of total contract price as security deposit for faithful performance of the contract. Such contract deposit shall be either in the form of Demand draft or tenderer shall pay such contract deposit online & same shall be refunded on successful completion of the work. However the contractor shall have to submit bankers Guarantee (BG) of equivalent amount valid for a period of one year against which the contract deposit shall be refunded.

BRIHANMUMBAI MAHANAGARPALIKA

Sub-Temporary Arrangment of CCTV Camera ,lighting and PA system at at Charai Talav for DASARA Festival 2024 in M/W Ward

BOQ

Sr.no	Description	Qty	Unit	Rate	Amount
1	Supply, Installation, Testing, Commissioning & Operational Activities for 1 Days of InfraRed Analog HD Outdoor Bullet camera, 1/3" CMOS image sensor, Fixed Lens: 3.6mm (2.8mm, 6mm & upto 12mm optional lens), Minimum 720 P lines horizontal resolution, IR Range upto 20m,1 channel BNC HDCVI high definition video output, Minimum Illumination: 0.05Lux/F2.0, OLux IR ON; Auto(ICR) / Color / B/W filter and etc. to fullfill the requirement.	12	Nos		
2	Supply, Installation, Testing, Commissioning & Operational Activities for 1 Days of HD Digital Video Recorder: 4 CHANNEL AHD front-end real-time encoding, 2 audio inputs and 1 audio outputs, Simultaneous live viewing, recording, playback, and remote streaming, VGA, HDMI, PTZ, USB Interface. 10/100Base-T Ethernet port for local or	2	Nos		
3	Supply, Installation, Testing, Commissioning & Operational Activities for 1 Days of 42inches LED monitor, Full HD Resolution, Backlight LED, Brightness: 400n NITS min., Contrast: 1200: 1 or better., Power supply: 230 ±10%, 50 Hz.	2	Nos		
4	Supply, Installation, Testing, Commissioning & Operational Activities for 1 Days of 4TB Storage (HDD)	2	Nos		
5	Supply, Installation, Testing, Commissioning & Operational Activities for 1 Days required Electrical Power Supply Arrangement	2	Job		
6	Supply, Installation, Testing, Commissioning & Operational Activities for 1Days of CAT 6 Cable, and lighting cable ,Signal cables etc.	2	Job		
7	Electrician - 2 Attendants at 2 sites for 3 Shifts for 10 Days	120	Nos		
		Total			
		SGST9%			
		CGST 9%			
		Grand Total			

Vender Code -

Bank Details -